

MV "APJ PRITI 2"

DRAUGHT SURVEY REPORT

PGUA/DS/294/25

CONTENTS	PAGE
1) PERSONS CONTACTED/ WITNESSES:	02
2) SHIP'S PARTICULARS	03
3) HOLD'S CAPACITIES / CARGOES / QUANTITIES / SF	03
4) SHIP'S HYDROSTATIC AND TANKS SOUNDING TABLES:	03
5) LOAD LINES	04
6) INITIAL DRAUGHT SURVEY DETAILS	04
7) FINAL DRAUGHT SURVEY DETAILS	04
8) CARGO PARTICULARS	04
9) DRAUGHT SURVEY CERTIFICATE	05
10) INITIAL BALLAST CONDITION	06
11) FINAL BALLAST CONDITION	06
12) INITIAL FRESH WATER CONDITION	07
13) FINAL FRESH WATER CONDITION	07
14) CONSUMABLES / OILS	07

ANNEXES

- SHIP'S PARTICULARS;
- CREW LIST;
- PRE-STOWAGE PLAN;
- LOADING SEQUENCE;
- DRAUGHT SURVEY CERTIFICATE
- FINAL CARGO PLAN;
- DETAILED CARGO PLAN PER LOADING TERMINAL;
- LINK TO THE DIGITAL DOCUMENTATION, PHOTOGRAPHS AND VIDEOS;



MV "APJ PRITI 2"

PGUA/DS/294/25
DRAUGHT SURVEY REPORT

THIS IS TO CERTIFY THAT the undersigned marine surveyor did, in compliance with instructions received from:

Messrs. AGTL - Armazéns Gerais Terminal Ltda., Messrs. Cimbessul Terminal Portuario S/A, Messrs. Cotriguaçu Cooperativa Central Regional Iguaçu Ltda., Messrs. Rocha Terminais Portuários e Logística .

Attend on board the referenced vessel on October 1st, 2025 from 8:20 until 10:20 hours, whilst she was anchored at inner roads area 8.3, and on October 6th, 2025 from 7:30 until 10:30 hours, whilst she was berthed alongside wharf 213 at port of Paranaguá, Br - Brazil, with views to perform the initial and final draft surveys, ascertaining the following figures:

1) PERSONS CONTACTED/ WITNESSES:

During the present survey, the following persons were contacted:

MV "APJ PRITI 2"

Mr. Prabhu Ramachandran, the Master
Mr. Rishab Misra, the Chief Officer
Mr. Manas Kumar Pramanik, the Chief Engineer

AGÊNCIA MARITIMA CARGONAVE LTDA
(As Local Agents)

Mr. Rafael Nogueira
Mr. Renan Calixto
Mr. Lorrain Gabriel Florentino

AGÊNCIA MARITIMA CARGONAVE LTDA
(As Port Operators)

Mr. Azemir do Rosario
Mr. Willian Cordeiro

VAN HERP & FRUMENTO
(As Owners P&I surveyors)

Mr. João Helio Frumento Filho
Mr. Abilio Abreu

BRAZILIAN CUSTOMS SURVEYOR

Mr. Marcio Augusto Zanicoski de Araujo

STANDARD BRAZIL MARINE SURVEYS
& SERVICES LTDA.

Mr. José Antônio M. G. Pereira
the undersigned marine surveyor
Mr. Igor do Carmo C. Pinotti



2) SHIP'S PARTICULARS:

Vessel: APJ PRITI 2
 Call sign: ATEL2
 Port of Register: Kolkata
 Flag: Indian
 IMO: 9401477
 LOA: 228,99
 LBP: 222,00
 Depth: 20,03
 Breadth: 32,26
 GRT: 43.168,0
 NRT: 27.291,0
 Classification: BV: MS*, BC-A, ESP, MNS*, M0.
 Light Ship: 11.226,4
 Summer deadweight/draft: 82554,00 on 14,72900 m

Shipyard: Tsuneish Shipbuilding Co. Ltd., - Japan

Owners: Apeejay Shipping Limited. - India
 Operators: Apeejay Shipping Limited. - India

3) HOLD'S CAPACITIES / CARGOES / QUANTITIES / SF

Hold	Capacity (cub.ft.)	Cargo	Quantity loaded (t) Exp. Corridor	SF
no.1	430.313,0	Soybeans	8.899,880	48,35
no.2	505.788,0	Soybeans	10.607,225	47,68
no.3	502.511,0	Soybeans	10.505,005	47,84
no.4	506.587,0	Soybeans	10.646,770	47,58
no.5	503.158,0	Soybeans	10.589,290	47,52
no.6	521.744,0	Soybeans	10.535,295	49,52
no.7	462.026,0	Soybeans	9.007,487	SLACK
Total	3.432.127,0		70.790,952	

4)SHIP'S APPROVED HYDROSTATIC AND TANKS SOUNDING TABLES:

Hydrostatic table: Issued by Tsuneish Shipbuilding Co. Ltd.
 on 07.12.2006, Dwg. No. 11202
 Approved by NK on 15.12.2006

Sounding table: Issued by Tsuneish Shipbuilding Co. Ltd.
 on 29.11.2006 Dwg. no. 13102-1/2



5) LOAD LINES

	FB (m)	Draught (m)	Displ. (t)	DWT (t)
Tropical Fresh Water:	5,023	15,063	95.836,4	84.610,0
Fresh Water:	5,323	14,763	93.780,4	82.554,0
Tropical:	5,357	14,729	95.886,4	84.660,0
Summer:	5,657	14,729	93.780,4	82.554,0
Winter:	5,957	14,129	91.674,4	80.448,0

6) INITIAL DRAUGHT SURVEY DETAILS:

Date: October 1st, 2025 from 8:20 until 10:20 hrs
 Place : Paranaguá, Br - Brazil (inner roads 8.3)
 Waves: 0,15 m
 Beaufort scale Wind force: 01
 Tide: Flood tide, 1knot
 Weather: Cloudy

7) FINAL DRAUGHT SURVEY DETAILS:

Date: October 6th, 2025 from 7:30 until 10:30 hrs
 Place : Paranaguá, Br - Brazil (wharf 213)
 Waves: 0,15 m
 Beaufort scale Wind force: 01
 Tide: Ebb tide, 1knot
 Weather: Misty

8) CARGO PARTICULARS:

Cargo: Soybeans in bulk
 Port of Loading: Port of Paranaguá, Br - Brazil
 Port of Discharge: Dalian, China
 Last cargo: SBM in bulk
 Last Port: Koh Sichang, Thailand

Shore Scales Figures: 70.790,952 t

Draught Survey Figures: STANDARD BRAZIL: 70.793,224 t
 MASTER/ CHIEF OFFICER: 70.795,000 t
 CUSTOMS SURVEYOR : 70.891,849 t
 OWNERS P&I SURVEYOR: 70.796,969 t



MV "APJ PRITI 2"	INITIAL SURVEY		FINAL SURVEY		
	Inner roads 8.3		Wharf 213		
	01.10.2025 - 08:25 h		06.10.2025 - 07:50 h		
	0,15 m. waves		0,15 m. waves		
IMO NO. 9401477	FLAG: Indian	BUILD: 2006		Wind force 01	Wind force 01
DRAUGHT SURVEY CERTIFICATE				Flood tide, 1knot	Ebb tide, 1knot
PGUA/DS/294/25				Weather: Cloudy	Weather: Misty
DRAUGHT		INITIAL		FINAL	
Forward port		4,1700 m		13,0100 m	
Forward starboard		4,2000 m		13,1300 m	
Forward mean		4,1850 m		13,0700 m	
Stern correction		-0,0431 m		-0,0046 m	
Draught forward (corrected to fore perpendicular)		4,1419 m		13,0654 m	
Midship port		5,2500 m		13,2200 m	
Midship starboard		5,2700 m		13,4000 m	
Midship mean		5,2600 m		13,3100 m	
Midship correction		0,0000 m		0,0000 m	
Draught midship (corrected to midship perpendicular)		5,2600 m		13,3100 m	
Aft port		6,4300 m		13,2700 m	
Aft starboard		6,4300 m		13,3500 m	
Aft mean		6,4300 m		13,3100 m	
Stern correction		0,1062 m		0,0114 m	
Draught after (corrected to after perpendicular)		6,5362 m		13,3214 m	
Kell correction		0,0000 m		0,0000 m	
Waterplane coefficient correction for hull deflexion		0,0083 m		-0,0170 m	
Means of means corrected for deflexion:		5,2880 m		13,2638 m	
True trim		BY STERN	2,39 m	BY STERN	0,26 m
Heel (angle & in cm)		S 000 °	2,00 cm	S 000 °	18,00 cm
Hull deflexion:		HOGGING	7,91 cm	SAGGING	11,66 cm
DISPLACEMENTS		INITIAL		FINAL	
Displacement in salt water		32.110,8 t		85.617,4 t	
First trim correction		-587,0 t		14,3 t	
Second trim correction		25,6 t		0,1 t	
Displacement corrected for trim		31.549,5 t		85.631,8 t	
Water density		1,02000		1,01950	
Displacement corrected for density		31.395,6 t		85.172,3 t	
Deductibles (fresh water, oils, etc.)		19.648,0 t		2.606,0 t	
Displacement corrected for deductibles		11.747,6 t		82.566,3 t	
Light Ship		11.226,4 t			
Calculated constant		546,7 t			
Anchor + chain		25,5 t		0,0 t	
Total cargo loaded on board as per draught survey				70793,2 t	
Loading terminals: AG, CB, CT, RO, SV, .		TPC	63,8 t/cm	TPC	69,9 t/cm
Cargo: Soybeans in bulk		MTC +0.5	923,9 t*cm	MTC +0.5	1195,9 t*cm
Paranaguá, Br - Brazil. October 6th, 2025		MTC -0.5	904,0 t*cm	MTC -0.5	1186,7 t*cm
Total cargo loaded on board as per shore scales				70.790,952 t	
Total cargo loaded on board as per draught survey				70.793,224 t	
Surplus				2,272 t 0,00 %	

Remarks: 1) Due to huge hull deflexion in sagging on final draft survey, it was applied the waterplane area coefficient correction for the deflexion formula as per UN/ECE/Energy/1992. 2) According to the Master/Chief Officer usual constant would amount to 400 t.

Standard Brazil Marine Surveys & Services Ltda
José Antonio Machado Gomes Pereira / Igor do Carmo C. Pinotti
Licensed Marine Officer / Marine Surveyor / 375460MM

Master/Ch. Off: 70.795,000 t 4,048 t 0,01 %
Customs : 70.891,849 t 100,897 t 0,14 %
Owners P&I: 70.796,969 t 6,017 t 0,01 %

10) INITIAL BALLAST CONDITION:

Date / Time : 01.10.25 /

08:40 h

Trim: 2,39 m

Vessel's	Observed	Pipe	Observed	Correction (m)		Corrected	Observed	Observed	Weight
Tank No.	Height (m)	A.D.L (m)	Sound. (m)	Trim	List	Sound. (m)	Volu. (m3)	Density	Total (t)
F.PK	20,42	0,28	9,20	0,00	0,00	9,20	1485,20	1,025	1522,30
1 WBT (P)	20,54	0,06	20,27	-0,15	0,00	20,12	1407,60	1,025	1442,80
1 WBT (S)	20,48	0,00	20,02	-0,13	0,00	19,89	1369,10	1,025	1403,30
2 WBT (P)	20,79	0,32	1,27	-0,13	0,00	1,14	467,70	1,025	479,40
2 WBT (S)	21,13	0,32	1,23	-0,13	0,00	1,10	451,10	1,025	462,40
3 WBT (P)	20,82	0,32	20,35	-0,32	0,00	20,03	3100,30	1,025	3177,80
3 WBT (S)	21,00	0,32	19,72	-0,29	0,00	19,43	2873,00	1,025	2944,80
4 WBT (P)	20,52	0,06	20,45	-0,32	0,00	20,13	2459,60	1,025	2521,10
4 WBT (S)	20,48	0,00	20,52	0,00	0,00	20,52	2540,80	1,025	2604,30
5 WBT (P)	21,22	0,32	10,43	-0,02	0,00	10,41	588,30	1,025	603,00
5 WBT (S)	21,24	0,32	20,13	-0,14	0,00	19,99	1166,50	1,025	1195,70
SLOP (P)	6,11	0,58	0,15	0,00	0,00	0,15	0,10	1,000	0,10
A.PK	13,02	0,35	1,27	0,02	0,00	1,29	22,20	1,000	22,20
TOTAL							17931,50		18379,20

11) FINAL BALLAST CONDITION:

Date / Time : 06.10.25 /

08:15 h

Trim: 0,26 m

Vessel's	Observed	Pipe	Observed	Correction (m)		Corrected	Observed	Observed	Weight
Tank No.	Height (m)	A.D.L (m)	Sound. (m)	Trim	List	Sound. (m)	Volu. (m3)	Density	Total (t)
F.PK	20,42	0,28	2,35	0,00	0,00	2,35	275,70	1,025	282,60
1 WBT (P)	20,54	0,06	0,00	0,00	0,00	0,00	3,50	1,025	3,60
1 WBT (S)	20,48	0,00	0,75	0,00	0,00	0,75	242,10	1,025	248,20
2 WBT (P)	20,79	0,32	0,18	0,00	0,00	0,18	70,70	1,025	72,50
2 WBT (S)	21,13	0,32	0,04	0,00	0,00	0,04	20,00	1,025	20,50
3 WBT (P)	20,82	0,32	0,13	0,00	0,00	0,13	102,60	1,025	105,20
3 WBT (S)	21,00	0,32	0,02	0,00	0,00	0,02	24,70	1,025	25,30
4 WBT (P)	20,52	0,06	0,86	0,00	0,00	0,86	321,60	1,025	329,60
4 WBT (S)	20,48	0,00	0,30	0,00	0,00	0,30	99,70	1,025	102,20
5 WBT (P)	21,22	0,32	0,46	0,00	0,00	0,46	56,40	1,025	57,80
5 WBT (S)	21,24	0,32	0,20	0,00	0,00	0,20	20,40	1,025	20,90
SLOP (P)	6,11	0,58	0,15	0,00	0,00	0,15	0,10	1,000	0,10
A.PK	13,02	0,35	1,44	0,00	0,00	1,44	29,00	1,000	29,00
TOTAL							1266,50		1297,50



12) INITIAL FRESH WATER CONDITION:

Vessel's	Observed	Pipe	Observed	Correction (m)		Corrected	Observed	Observed	Weight
Tank No.	Height (m)	A.D.L (m)	Sound. (m)	Trim	List	Sound. (m)	Volu. (m3)	Density	Total (t)
DWT (P)				GAUGE			67,00	1,000	67,00
FWT (S)							78,00	1,000	78,00
TOTAL							145,00		145,00

13) FINAL FRESH WATER CONDITION:

Vessel's	Observed	Pipe	Observed	Correction (m)		Corrected	Observed	Observed	Weight
Tank No.	Height (m)	A.D.L (m)	Sound. (m)	Trim	List	Sound. (m)	Volu. (m3)	Density	Total (t)
DWT (P)				GAUGE			136,00	1,000	136,00
FWT (S)							64,00	1,000	64,00
TOTAL							200,00		200,00

14) DEDUCTIBLES

	INITIAL	FINAL
INTERMEDIATE FUEL OIL	977,6 t	977,6 t
MARINE DIESEL OIL	146,2 t	130,9 t
LUBRICATING	K	K
FRESH WATER	145,0 t	200,0 t
BALLAST	18379,2 t	1297,5 t
OTHERS	0,0 t	0,0 t
TOTAL	19648,0 t	2606,0 t



Digital documentation, photographs and videos:

MV APJ PRITI 2

<https://standardbrazil.com.br/atendimentos/link?tag=PGUA/DS/294/25&tk=3395009241>



MV APJ PRITI 2

PRINCIPAL PARTICULARS				PREVIOUS NAME:		PASCHA/STAR DANAI	
OWNERS:	APEEJAY SHIPPING LIMITED, KOLKATA, INDIA			OPERATOR:	APEEJAY SHIPPING LIMITED, KOLKATA		
FLAG	INDIA		PORT OF REGISTRY:		KOLKATA		
IMO:	9401477		MMSI:		419002044	CALL SIGN:	ATEL2
BUILDERS:	TSUNEISHI SHIPBUILDING CO. LTD., JAPAN					OFFICIAL NO.:	5074
YARD NO:	1394	KEEL LAID:	03-Mar-06	LAUNCHED:	21-Oct-06	DELIVERED:	15-Dec-06
CLASS:	BV & IR(LL)						
TONNAGES:				P & T CLUB			
LIGHTSHIP:	11226.4 MT	SUEZ CANAL GRT:	44538.99 MT	NORTHSTANDARD			
GRT	43168 MT	SUEZ CANAL NRT:	41545.28 MT				
NRT	27291 MT	PAN. CANAL GRT:	43158.00 MT	HATCH COVERS			
SUEZ CNL ID:	37384	PAN. CANAL NRT:	35642.00 MT	McGregor SIDE ROLLING			
		F. BRD (m)	DRAFT (m)	D.W. (MT)	DISPL. (MT)	TPC (MT)	FWA (MM)
T. FRESH (TF):		5.023	15.063	84,610.00	95,836.00	70.27	
FRESH (F):		5.323	14.763	82,554.00	93,780.00	70.24	
TROPICAL (T):		5.357	14.729	84,660.00	95,886.00	70.24	
SUMMER (S):		5.657	14.429	82,554.00	93,780.00	70.21	334.00
WINTER (W):		5.957	14.129	80,448.00	91,674.00	70.14	
DIMENSIONS:		TANK TOP MEASUREMENT:(L X FWD BEAM X AFT BEAM)					
LENGTH OVERALL (LOA):		228.99 m		NO. 1	24m X 8.40m X 23.80 m		
LENGTH B.P. (LBP):		222.00 m		NO. 2 & 5	24m X 23.80 m		
BREADTH MOULDED (BM):		32.26 m		NO. 6	25m X 23.80 m		
DEPTH MOULDED (DM):		20.03 m		NO.7	23m X 23.8m X 10.40m		
HATCH SIZES:					TANK TOP STRENGTH:		
NO. 1		L 14.24 m X B 13.80 m		NO. 1 -3- 5-7		29.80 MT / m ²	
NO. 2 - 7		L 17.80 m X B 15.40 m		NO. 2 -4-6		20.00 MT / m ²	
HATCH COVER STRENGTH (SEA LOAD):					DISTANCES:		
NO. 1		2.08 MT / m ²	NO.2-7	1.75 MT / m ²	HEIGHT FROM KEEL TO RADAR MAST:		52.88 m
HEIGHT FROM M/DECK CENTERLINE TO TOP H/C				2.18 M	UNDER KEEL TO HATCH COVER TOP NO. 1 - 7		23.054 m
PARALLEL BODY LENGTH:				158 m	ACCOMMODATION FRONT WALL TO BOW		200.04 m
MAIN ENGINE: MITSUI MAN B&W 7S50MC-C X 1 SET					ACCOMMODATION FRONT WALL TO STERN		28.95 m
CMCR:		9800 KW X 113 RPM OR 13315 HP		FROM BOW TO FWD NO. 1 H.		20.00 m	
PROPELLER		F.P.P. KEYLESS (KIS) 1 SET (4 BLADES, DIA. 6.3 m)		FROM STERN TO AFT NO. 7		34.50 m	
TYPE OF SHIP:		BULK CARRIER - FLUSH DECK WITH FORECASTLE		FROM FWD NO. 1 TO AFT NO. 7 H.		174.49 m	
TOTAL HOLD'S GRAIN CAPACITY				DIST KEEL TO COMPASS/BRIDGE DECKS		36.73/34.08 m	
INCL HATCH SPACES				UNDER KEEL TO MAINDECK CENTERLINE		20.80 m	
HOLDS	m ³	ft ³	m ³	ft ³	TANK CAPACITY:		
	97,186.10	34,32,127	2,121.80	74,933	TOTAL FUEL OIL CAPACITY 85% FULL:		
					2082.07 m ³		
					IFO SPECS RMG 380 As per ISO 8217 2010		
1	12,185.00	4,30,313.00	223.40	7,889.00	TOTAL DIESEL OIL CAPACITY 85%:		DMA distillate
2	14,322.20	5,05,788.00	316.40	11,174.00	HEAVY BALLAST:		621.18 m ³
3	14,229.40	5,02,511.00	316.40	11,174.00	LIGHT BALLAST		FRESH WATER:
4	14,344.80	5,06,587.00	316.40	11,174.00			479.4 M3
5	14,247.70	5,03,158.00	316.40	11,174.00	CONTACT DETAILS	FBB250 :	+870 773 945 389
6	14,774.00	5,21,744.00	316.40	11,174.00		V-SAT1 :	+47 2240 8417
7	13,083.00	4,62,026.00	316.40	11,174.00		V-SAT2 :	+47 2240 8418
TTL	97,186.10	34,32,127.00	2,121.80	74,933.00		INM-C No.1	441930325
				EMAIL:	aslops@apeejaygroup.com		



CAPT. R.PRABHU
MASTER OF MV APJ PRITI 2

CREW LIST

1. Name of ship : APJ PRITI 2		2. Port of Departure : SINGAPORE			3. Date of Departure : 19.08.2025			07. Call Sign : ATEL2
4. Nationality of ship : INDIA		5. Port of Arrival : PARANAGUA,BRAZIL			6. Date of Arrival :22.09.2025			08. GRT : 43168
9. SL No	10. Family Name Given Name	11. Sex	12. Rank	13. Nationality	14. Date & Place of Birth	15. Passport No./Expiry date	16. seaman book / expiry date	17. Place and date of signed on
1	RAMACHANDRAN PRABHU	M	Master	INDIAN	02.05.1977 / TIRUVALLUR,TAMIL NADU	AD957429 / 23.06.2035	MS 12403 / 25.04.2032	KOH SI CHANG / 12.08.2025
2	MISRA RISHAB	M	Ch. Officer	INDIAN	06.02.1990 / AMRITSAR,PUNJAB	AB827087 / 09.06.2035	MUM166378 / 18.03.2030	KOH SI CHANG / 12.08.2025
3	PATNAIK MANTRI SRIDHAR	M	2nd Officer	INDIAN	24.07.1979/ KHARAGPUR, WEST BENGAL	ZA167947 / 16.07.2035	MUM 113054 / 29.07.2035	KOH SI CHANG / 12.08.2025
4	THIRUMOORTHY ARUNPANDI	M	3rd Officer	INDIAN	03.09.1997 / ARUPPUKOTTAI,TAMIL NADU	R0091672 / 03.05.2027	MUM292984 / 08.01.2028	KOH SI CHANG / 12.08.2025
5	TIWARI DEVANSH	M	CADET	INDIAN	21.11.2003 / BHATAPARA,CHHATTISGARH	U8632925 / 01.05.2032	MUM 546349 / 20.03.2034	KOH SI CHANG / 12.08.2025
6	PRAMANIK MANAS KUMAR	M	Ch. Engr	INDIAN	26.01.1966 / RADHANAGAR, WEST BENGAL	S5336186 / 10.07.2028	CL 72265 / 23.06.2030	KOH SI CHANG / 12.08.2025
7	TIWARI SUMIT	M	2nd Engr	INDIAN	02.02.1986/ KANPUR,UTTAR PRADESH	ZA032566 / 14.04.2035	MUM144258 / 07.04.2031	KOH SI CHANG / 12.08.2025
8	RAM VIVEK	M	3rd Engr	INDIAN	20.05.1997 / KOLKATA, WEST BENGAL	S8868132 / 14.11.2028	KOL114837 / 10.04.2029	KOH SI CHANG / 12.08.2025
9	CHOUHEY SAGAR	M	4th Engr	INDIAN	03.07.1997 / KULTI, WEST BENGAL	Y1584504 / 16.04.2034	KOL130928 / 04.08.2032	KOH SI CHANG / 12.08.2025
10	MONDAL SHIBADITYA	M	TME	INDIAN	24.08.2003 / KOLKATA, WEST BENGAL	Z6424857 / 04.10.2031	KOL164427 / 25.09.2034	KOH SI CHANG / 12.08.2025
11	MEEGADA AJAYA VARDHANA REDDY	M	Asst. ETO	INDIAN	22.12.1996 / HYDERABAD, TELANGANA	X6973266 / 15.03.2033	MUM439164 / 06.06.2033	SINGAPORE / 18.08.2025
12	TIWARI SARVESH KUMAR	M	Dk Fitter	INDIAN	08. 07.1972 / NUKUROI PUR,UTTAR PRADESH	C2747952 / 10.09.2034	MUM138823 / 02.04.2033	KOH SI CHANG / 12.08.2025
13	IFRAN MOHAMMAD	M	Eng Fitter	INDIAN	05.01.1989/ MAHARAJGANJ,UTTAR PRADESH	T1176355 / 23.05.2029	CH106475 / 03.04.2027	KOH SI CHANG / 12.08.2025
14	ALI AHMED	M	BOSUN	INDIAN	08.12.1970 / KOLKATA, WEST BENGAL	X4839327 / 07.04.2034	CL 48166 / 15.08.2028	KOH SI CHANG / 12.08.2025
15	KESARWANI AJEET KUMAR	M	AB 1	INDIAN	15.07.1995 / ALLAHABAD,UTTAR PRADESH	AB333560 / 29.06.2035	MUM324036 / 06.08.2028	KOH SI CHANG / 12.08.2025
16	MANDLEKAR SHAIBAJ BABAMIYAN	M	AB 2	INDIAN	12.12.1991 / MHAPRAL MANDANGADH, MAHARASHTRA	V3946803 / 12.10.2031	MUM206212 / 30.01.2032	KOH SI CHANG / 12.08.2025
17	PRADHAN ROHIT	M	AB 3	INDIAN	18.12.1991 / RANCHI ,JHARKHAND	Z6296335 / 05.08.2031	MUM440848 / 28.09.2031	KOH SI CHANG / 12.08.2025
18	SAHA SAPTARSHI	M	OS	INDIAN	12.01.2003 / KOTRANG, WEST BENGAL	W1237980 / 29.06.2032	KOL133702 / 10.11.2032	KOH SI CHANG / 12.08.2025
19	MOHAMMAD SALIK	M	TR OS	INDIAN	25.01.2000 / HOWRAH, WEST BENGAL	B6208332 / 29.11.2033	KOL164952 / 09.10.2034	KOH SI CHANG / 12.08.2025
20	BISWAL SUDHANSHU SEKHAR	M	OILER 1	INDIAN	27.01.2000 / KABISURYANAGAR, ODISHA	S9077680 / 23.06.2029	MUM 423630 / 05.01.2031	KOH SI CHANG / 12.08.2025
21	KUMAR PRAMIT	M	OILER 2	INDIAN	05.02.1988 / CHAPRA, BIHAR	ZA119974 / 02.07.2035	CL55569 / 23.07.2035	KOH SI CHANG / 12.08.2025
22	KAUSHAL RAHUL	M	OILER 3	INDIAN	22.12.1994 / MUBARIKPUR, HIMACHAL PRADESH	R6819254 / 05.02.2028	MUM342128 / 31.10.2028	KOH SI CHANG / 12.08.2025
23	PRATHEEP FERNANDO PRAVIEN FERNANDO	M	WIPER	INDIAN	09.08.1997 / THOOTHUKUDI, TAMIL NADU	C3945232 / 24.10.2034	MUM370711 / 07.03.2029	KOH SI CHANG / 12.08.2025
24	DOLAI DIPAK	M	COOK	INDIAN	02.02.1977 / MIDNAPORE, WEST BENGAL	P7926501 / 15.02.2027	CL29210 / 27.07.2035	KOH SI CHANG / 12.08.2025
25	MANPREET SINGH	M	GS	INDIAN	18.06.1993 / GHARUAN, PUNJAB	V4157814 / 14.11.2031	MUM219722 / 08.11.2032	KOH SI CHANG / 12.08.2025

IMO Convention on Facilitation of International Maritime Traffic



MASTER
M.V APJ PRITI 2



CARGO LOADING / DISCHARGING PLAN

Page 1 of 2

Loading or Unloading Plan Version No.:		Date: 30/09/2025		Vessel: APJ PRITI 2		Cargo: SOYA BEAN		Voyage No.: 001 B					
						Last Cargo: SBM							
Load/Unload Port: PARANAGUA, BRAZIL				Assumed stowage factor : 48.5 FT3/MAT		Ballast pumping rate: 950x2 m3/hr		Dock water density: 1.015		Max draught available (HW): 13.30		Max air draught in berth: 18.0	
To/From Port: DALIAN, CHINA				No. of loaders/ dischargers: 2		Load/discharge rate: 1000 mt/Hr X 2				Min draught available (LW): 13.30		Max sailing/arrival draught: 13.30	
<u>Hold No-1</u> Grade:		<u>Hold No-2</u> Grade:-		<u>Hold No-3</u> Grade:-		<u>Hold No-4</u> Grade:-		<u>Hold No-5</u> Grade:-		<u>Hold No-6</u> Grade:-		<u>Hold No-7</u> Grade:-	
SOYA		SOYA		SOYA		SOYA		SOYA		SOYA			
BEAN		BEAN		BEAN		BEAN		BEAN		BEAN			
Qty:-		Qty:-		Qty:-		Qty:-		Qty:-		Qty:-			
8955		10585		10515		10490		10520		10920		8800	
MT		MT		MT		MT		MT		MT			

Pour No.	Cargo		Ballast Operations	Time required (hours)	Comments	Calculated Values				Calculated Values			Observed Values		
	Hold No.	Tonnes				Draught		Maximum		Air draught	Draught mid	Trim	Draught		
						Fwd	Aft	BM*	SF*				Fwd	Aft	Mid
					BERTHING CONDITION	4.30	6.80	58	27	18.0	5.55	2.30			
1A	2	5000	PO WBT 2 P/S - EMPTY	2.5	Balance: 5,585 MT					16.80					
1B	6	5000	PO WBT 5P/S - EMPTY		Balance: 5,920 MT	6.12	7.02	57	30	16.60	6.57	0.90			
2A	3	5000	PO WBT 3 P/S - EMPTY	2.5	Balance: 5,515 MT					16.40					
2B	5	5000			Balance: 5,520 MT	6.44	8.01	48	42	15.90	7.22	1.58			
3A	4	5000	PO WBT 4 P/S - EMPTY	2.5	Balance: 5,490 MT					15.30					
3B	7	5000			Balance: 3,800 MT	6.36	9.81	46	17	13.70	8.08	3.45			
4A	1	5000	PO WBT 1 P/S - EMPTY	2.5	Balance: 3955 MT					16.30					
4B	4	5490	PO FPT – UPTO 23%		LOADING COMPLETE	7.89	10.21	26	34	15.10	9.05	2.32			
5A	2	4585	STRIPPING	3.0	Balance: 1000 MT					14.70					
5B	6	4920	STRIPPING		Balance: 1000 MT	9.55	11.32	54	18	13.50	10.75	1.71			
6A	3	5515	STRIPPING	2.5	LOADING COMPLETE					11.70					
6B	7	3800	STRIPPING		LOADING COMPLETE	10.61	12.96	46	33	12.20	11.79	2.34			

	INITIAL SURVEY	FINAL SURVEY		
MV "APJ PRITI 2"	Inner roads 8.3	Wharf 213		
	01.10.2025 - 08:25 h	06.10.2025 - 07:50 h		
	0,15 m. waves	0,15 m. waves		
IMO NO. 9401477 FLAG: Indian BUILD: 2006	Wind force 01	Wind force 01		
DRAUGHT SURVEY CERTIFICATE	Flood tide, 1knot	Ebb tide, 1knot		
PGUA/DS/299/25	Weather: Cloudy	Weather: Misty		
DRAUGHT	INITIAL	FINAL		
Forward port	4,1700 m	13,0100 m		
Forward starboard	4,2000 m	13,1300 m		
Forward mean	4,1850 m	13,0700 m		
Stern correction	-0,0431 m	-0,0046 m		
Draught forward (corrected to fore perpendicular)	4,1419 m	13,0654 m		
Midship port	5,2500 m	13,2200 m		
Midship starboard	5,2700 m	13,4000 m		
Midship mean	5,2600 m	13,3100 m		
Midship correction	0,0000 m	0,0000 m		
Draught midship (corrected to midship perpendicular)	5,2600 m	13,3100 m		
Aft port	6,4300 m	13,2700 m		
Aft starboard	6,4300 m	13,3500 m		
Aft mean	6,4300 m	13,3100 m		
Stern correction	0,1062 m	0,0114 m		
Draught after (corrected to after perpendicular)	6,5362 m	13,3214 m		
Kell correction	0,0000 m	0,0000 m		
Waterplane coefficient correction for hull deflexion	0,0083 m	-0,0170 m		
Means of means corrected for deflexion:	5,2880 m	13,2638 m		
True trim	BY STERN 2,39 m	BY STERN 0,26 m		
Heel (angle & in cm)	S 000 ° 2,00 cm	S 000 ° 18,00 cm		
Hull deflexion:	HOGGING 7,91 cm	SAGGING 11,66 cm		
DISPLACEMENTS	INITIAL	FINAL		
Displacement in salt water	32.110,8 t	85.617,4 t		
First trim correction	-587,0 t	14,3 t		
Second trim correction	25,6 t	0,1 t		
Displacement corrected for trim	31.549,5 t	85.631,8 t		
Water density	1,02000	1,01950		
Displacement corrected for density	31.395,6 t	85.172,3 t		
Deductibles (fresh water, oils, etc.)	19.648,0 t	2.606,0 t		
Displacement corrected for deductibles	11.747,6 t	82.566,3 t		
Light Ship	11.226,4 t			
Calculated constant	546,7 t			
Anchor + chain	25,5 t	0,0 t		
Total cargo loaded on board as per draught survey		70793,2 t		
Loading terminals: AG, CB, CT, RO, SV, .	TPC	63,8 t/cm	TPC	69,9 t/cm
Cargo: Soybeans in bulk	MTC +0.5	923,9 t/cm	MTC +0.5	1195,9 t/cm
Paranaguá, Br - Brazil. October 6th, 2025	MTC -0.5	904,0 t/cm	MTC -0.5	1186,7 t/cm
Total cargo loaded on board as per shore scales			70.790,952 t	
Total cargo loaded on board as per draught survey			70.793,224 t	
Surplus	2,272 t		0,00 %	

Remarks: 1) Due to huge hull deflexion in sagging on final draft survey, it was applied the waterplane area coefficient correction for the deflexion formula as per UN/ECE/Energy/19/1992. 2) According to the Master/Chief Officer usual constant would amount to 400 t.

Standard Brazil Marine Surveys & Services Ltda.
 José Antonio Machado Gomes Pereira / Igor do Carmo C. Pinotti
 Licensed Marine Officer / Marine Surveyor / 375460MM

Master/Ch.Off: 70.795,000 t 4,048 t 0,01 %
 Customs : 70.891,849 t 100,897 t 0,14 %
 Owners P&I: 70.796,969 t 6,017 t 0,01 %



Master/Ch.Off:

www.standardbrazil.com.br



" MV APJ PRITI 2 "

	7	6	5	4	3	2	1
CARGO PLAN	SLACK SBS 8.800,000	FULL SBS 10.920,000	FULL SBS 10.520,000	FULL SBS 10.480,000	FULL SBS 10.515,000	FULL SBS 10.585,000	FULL SBS 8.955,000
LOADED	9.007,487	10.535,295	10.589,290	10.646,770	10.505,005	10.607,225	8.899,880
UNLOADED	-207,487	384,705	-69,290	-156,770	9,995	-22,225	55,120
TTL HLDG	9.007,487	10.535,295	10.589,290	10.646,770	10.505,005	10.607,225	8.899,880
CUBIC FEET	462,026	521,744	503,158	506,587	502,511	505,788	430,313
SF PROGRAMED	52,50	47,78	47,83	48,29	47,79	47,78	48,05
SF LOADED	51,29	49,52	47,52	47,58	47,84	47,68	48,35

Cmmd	Cargo Plan	Nominated	Loaded	To go to C. Plan	To go to Nom.
SBS	70.785,000	71.285,000	70.790,952	-5,952	494,048

		6-out		5:05		Hrs											
Shippers	Cmd	Holds	Qty	Ldd	To go	Terminal	Broker / Pool	1	2	3	4	5	6	7		COMMENCED	COMPLETED
ADM/GRANO	SBS	ALL	4.375,000	4.375,000		SV APPA	GRANO		1.660,450	2.714,550						04/10 - 23:30	05/03 - 03:20
ADM/TIB	SBS	ALL	4.375,000	4.375,000		SV APPA	TIBAGI	2.699,990	1.352,380				322,630			03/10 - 09:20	04/10 - 23:30
CARGILL/CT	SBS	ALL	6.000,000	6.000,000		COTRI	CT		5.034,470	965,530						03/10 - 06:25	04/10 - 02:50
ADM/CT	SBS	ALL	13.000,000	13.000,000		COTRI	CT			1.746,705	2.796,400	1.374,760	4.481,955	2.600,180		04/10 - 22:45	05/10 - 07:15
COFCO/CT	SBS	ALL	11.830,000	11.830,000		COTRI	CT			4.050,355	7.779,645					04/10 - 02:50	04/10 - 22:45
AMAGGI/PAG	SBS	ALL	4.000,000	4.000,000		AGTL	AG	2.341,470	1.658,530							04/10 - 13:25	04/10 - 19:30
ROYAL/CB	SBS	ALL	569,772	569,772		CIMBESSUL	CB							569,772		05/10 - 07:25	05/10 - 06:00
ADM/RO	SBS	ALL	8.935,000	8.440,952	494,048	ROCHA	RO	3.858,420	901,395	1.027,865	70,725	1.351,492	1.020,030	211,025		05/10 - 14:55	06/10 - 05:05
COFCO/RO	SBS	ALL	4.770,000	4.770,000		ROCHA	RO					2.856,323		1.913,677		04/10 - 18:05	05/10 - 14:55
AMAGGI/RO	SBS	ALL	4.000,000	4.000,000		ROCHA	RO					2.719,548	1.280,452			04/10 - 06:30	04/10 - 12:05
BUNGE/RO	SBS	ALL	6.000,000	6.000,000		ROCHA	RO					2.287,167		3.712,833		04/10 - 12:05	04/10 - 18:05
BTG/RO	SBS	ALL	3.000,000	3.000,000		ROCHA	RO						3.000,000			04/10 - 03:45	04/10 - 06:30
ROYAL/RO	SBS	ALL	430,228	430,228		ROCHA	RO							430,228		03/10 - 06:45	04/10 - 03:45
			71.285,000	70.790,952	494,048			8.899,880	10.607,225	10.505,005	10.646,770	10.589,290	10.535,295	9.007,487			

Shippers	Cmd	Holds	Qty	Ldd	To go	-	-	1	2	3	4	5	6	7	-	-
ADM	SBS	ALL	30.685,000	30.190,952	494,048			6.558,410	3.914,225	5.489,120	2.867,125	2.726,252	5.824,615	2.811,205		
CARGILL	SBS	ALL	6.000,000	6.000,000					5.034,470	965,530						
COFCO	SBS	ALL	16.600,000	16.600,000						4.050,355	7.779,645	2.856,323		1.913,677		
AMAGGI	SBS	ALL	8.000,000	8.000,000				2.341,470	1.658,530			2.719,548	1.280,452			
ROYAL	SBS	ALL	1.000,000	1.000,000									430,228	569,772		
BUNGE	SBS	ALL	6.000,000	6.000,000								2.287,167		3.712,833		
BTG	SBS	ALL	3.000,000	3.000,000									3.000,000			
			71.285,000	70.790,952	494,048			8.899,880	10.607,225	10.505,005	10.646,770	10.589,290	10.535,295	9.007,487		

Loading Periods

	/07*13	/13*19	/19*01	03/01*07	03/01*07	03/01*07	03/01*07
03/07*13	5.427,720	03/13*19	RAIN	03/19*01	RAIN	04/01*07	8.262,310
04/07*13	9.200,880	04/13*19	9.489,735	04/19*01	12.035,765	05/01*07	12.833,120
05/07*13	1.475,507	05/13*19	5.942,750	05/19*01	4.141,820	06/01*07	1.043,195
/07*13		/13*19		/19*01		/01*07	
/07*13		/13*19		/19*01		/01*07	
/07*13		/13*19		/19*01		/01*07	
							70.790,952

LAST SHIPPER: ADM/RO

TERMINAL	NOMINATED	LOADED	PERCENT LDD	TO GO
SV APPA	8.750,000	8.750,000	100,00%	
COTRI	30.830,000	30.830,000	28,38%	
AGTL	4.000,000	4.000,000	100,00%	
CIMBESSUL	569,772	569,772	100,00%	
ROCHA	27.135,228	26.641,180	98,18%	494,048
TOTAL	71.285,000	70.790,952	99,31%	494,048

NAVIO:	APJ PRITI 2
AGÊNCIA:	AGÊNCIA MARITIMA CARGONAVE LTDA
OPERADOR:	AGÊNCIA MARITIMA CARGONAVE LTDA
DATA EMBARQUE:	06.10.2025
PESO TERRA:	70.790,952
PESO BORDO:	70.793,224
VARIAÇÃO:	2,272
PERCENTUAL:	0,00%
Entrar na estatística	Sim

PORÃO	1	2	3	4	5	6	7	TOTAL
PRODUTO	Soybeans	Soybeans	Soybeans	Soybeans	Soybeans	Soybeans	Soybeans	
AGTL	2.341,470	1.658,530						4.000,000
CARGILL								0,000
CENTRO SUL								0,000
CIMBESSUL							569,772	569,772
COAMO								0,000
CORREDOR - V	2.699,990	3.012,830	2.714,550			322,630		8.750,000
CORREDOR - H								0,000
COTRIGUAÇU		5.034,470	6.762,590	10.576,045	1.374,760	4.481,955	2.600,180	30.830,000
INTERALLI								0,000
DREYFUS								0,000
ROCHA	3.858,420	901,395	1.027,865	70,725	9.214,530	5.730,710	5.837,535	26.641,180
TOTAL	8.899,880	10.607,225	10.505,005	10.646,770	10.589,290	10.535,295	9.007,487	70.790,952
CUBAGEM	430.313	505.788	502.511	506.587	503.158	521.744	462.026	
FATOR DE ESTIVA	48,35	47,68	47,84	47,58	47,52	49,52	51,29	
CONDIÇÃO PORÃO	FULL	FULL	FULL	FULL	FULL	FULL	SLACK	

Observações: